

JANUARY 28, 2019

ADDENDUM NO. 1

TO: CONTRACT DOCUMENTS
FOR: "BIG COTTONWOOD CANYON GAP TRAIL AND ROADWAY CONSTRUCTION --
PROJECT # CHC.294"-- CITY OF COTTONWOOD HEIGHTS, UTAH

A. BID SCHEDULES.

1. **BID SCHEDULE "A":** Revise Bid Schedule, item #8, page #00420 to read:
 - a. ITEM: Relocate Existing Street Light "
QUANTITY – 1,
LUMP SUM – \$4,000
 - b. Enter a Lump Sum price of \$4,000 for Bidding purpose
2. Revise Bid Schedule, item #23, page #00420 to read:
 - a. ITEM: "Reconstruct existing 4' x 3' concrete diversion box, complete, with wing walls; including all required earthwork, gravel base, connect to existing drainage channel"

B. SECTION 02100 - MEASUREMENT & PAYMENT.

1. Paragraph 1.03 MEASUREMENT & PAYMENT:.
 - a. Revise ITEM K to read the following:
- K. Relocate Existing Street Light (Bid Item No. 8):

Basis for Measurement: Separate Lump Sum for each individual item.

Basis for Payment: Includes all required earthwork for relocating existing street light, to include excavating for installing pole in new location, structural excavating, backfilling excavations, and compacting backfill material; removing existing wood street light with attached overhead power lines, complete; re-installing wood street light in its new location, as indicated and as directed; furnishing and installing, wires, junction boxes, and all appurtenant items, from the end of relocated street light to existing power lines; and all appurtenant work to complete relocation of existing street light.

GILSON ENGINEERING